Fastener Lengths: U-Build supplies standard fasteners as noted in our construction guide to match insulation conditions

noted @ order placing.

Standard Colours: For cladding and trim are based on current stock (see Colour Availability Chart).

Roof Panel Length: Maximum of 51'-0" for SSR and 42'-1" for Screw Down (longer requirements will be spliced).

Wall Panel Length: Maximum 42'-1" (longer requirements will be spliced).

Over Head Door Jambs: On top of curb (if applicable).

Walk Door Jambs : On top of curb (if applicable).

Cable Bracing: Is used whenever possible.

Base Angle or Channel: Supplied at base of building (indicate preference on quote).

Flange Bracing: Supplied as required on all girts and purlins.

Closures: Roof Panel: @ Eave.

@ Ridge for buildings with SSR or roof slopes greater than 4:12.

Closures: Wall Panel: *Indicate building insulation conditions @ quote / order placing.

*Insulated - closures @ gable ends, high and low eave (not gutter).

*Uninsulated - closures @ gable ends, high and low eave (not gutter), header and sills of

openings and base.

Sealer Tape: Supplied: @ Roof panel seams and splices, roof eave, ridge, and gable, and building base perimeter.

@ Wall panel and trim joints to 60" above low roof surface.

Formed Ridge Cap: Supplied for screw down roof panels (up to a maximum roof slope of 4:12).

Ridge Cap: Supplied for screw down roof with roof slopes greater than 4:12 (556305).

Supplied for SSR (554426).

Standard Trims: Base flashings on building perimeter (556337).

Overhead door trims for OH door perimeter (556303) or (556410).

Header flashings on framed opening headers (556339).

Primary eave trims on low eaves (556428).

Finished eave, gable, corner, and J trims - to suit panel profile.

Center gable cover c/wU-Build logo (except monoslope buildings c/w U-Build Sign Kit (139840)

Liner Packages Classification:

Economy: Trims supplied for framed openings, corners, (and top of wall panels for full height walls if ceiling

lined).

Standard: Trims supplied for framed openings, corners, top of wall panel, (and gable for full height walls if

ceiling lined).

Deluxe: Trims supplied for framed openings, corners, top of wall panel, along columns and rafters, (and

gable for full height walls if ceiling lined).

Vapour Barrier: Trims package same as deluxe with sealer tape on all seams, laps, ends and closures at panel ends.